



Municipality of Princeton

*Witherspoon Hall
400 Witherspoon Street
Princeton, NJ 08540-3496*

*Office of the Engineer
Telephone (609)921-7077
Facsimile (609) 688-2026*

*DEANNA STOCKTON, P.E., C.M.E.
Municipal Engineer
dstockton@princetonnj.gov*

**Neighborhood Meeting Notice for Water Main Replacement Project by
New Jersey American Water Company (NJAW)**

June 25, 2021

Dear Residents and Property Owners,

As part of New Jersey American Water's 2021 Capital Improvement Program, water mains and individual services in the municipal right of way will be replaced on the following streets starting late July and continuing through mid-September 2021:

- Leavitt Lane, (21) service transfers, 1,100 LF
- Fisher Avenue , (19) service transfers, 820 LF
- Stanley Ave , (11) service transfers, 660 LF

CRJ Contracting Corporation Inc. will be performing the installation for New Jersey American Water.

We invite you to attend a neighborhood virtual meeting on Thursday, July 15, 2021 at 7:00 PM to 8:00 PM with New Jersey American Water Company and their contractor, CRJ Contracting, to learn about the project, time schedule and temporary construction impacts.

Register in advance for this meeting:

https://us02web.zoom.us/meeting/register/tZUkc-2hrDoqHdRMGWfKoaVT3SG3DVpYHz7_

After registering, you will receive a confirmation email containing information about joining the meeting.

The existing water mains on the above mentioned streets date back to the early 1950's and are near the end of their lifecycle. Old unlined cast iron water mains have built up deposits that lead to discoloration, taste and odor issues and reduced fire flows to fire hydrants. These older pipes tend to fail, causing water main breaks in cold winter months and during the summer when demand is high.

In order for New Jersey American Water Company to provide high quality, reliable water service, CRJ Contracting will be:

- Replacing the water main in the street with new 8" ductile iron cement lined water main.
- Replacing all existing fire hydrants and adding additional hydrants if requested by the Fire Marshal.
- Replacing individual house service laterals to the curb line / edge of pavement.
- Installing water meter chambers near the curb line / edge of pavement where applicable for each residence.


- Restoring all disturbed areas including roadway resurfacing.

These water infrastructure upgrades will provide clean, dependable water service for many years to come. Construction is scheduled to begin in late July and be completed by early September. Property owners and residents will be notified in the near future of additional project details and the anticipated schedule for each individual street.

If you have questions or concerns, please contact the NJAW Inspector; if you require additional information, please feel free to contact the Engineering Department.

New Jersey American Water and the Municipality of Princeton appreciates your patience and tolerance as this infrastructure improvement project proceeds in your neighborhood.

Best regards,



Deanna Stockton, P.E., C.M.E.
Municipal Engineer

Contact Information:

New Jersey American Water

Luis DeAlmeida
Sr. Construction Inspector
(908) 455-2936

Luis.DeAlmeida@amwater.com

CRJ Contracting

Shane Abbott
Construction Manager
(609) 477-9631

NJAW Emergency

1-800-272-1325

Princeton Engineering Inspector

Richard Decker
(609) 751-6826

rdecker@princetonnj.gov

Princeton Construction Engineer

Ian Baker, E.I.T.
(609) 455-2555

ibaker@princetonnj.gov

Police Non-Emergency

(609) 921-2200